
	Generic Task Based Risk Assessment Working on Military Sites	Reference:	ISA 03 v14.0
	For: UK Power Networks Services	Review Dates:	01/11/2027

	STEPS	HAZARDS	Unmitigated			CONTROL MEASURES	Mitigated		
			C	L	R		C	L	R
	Movement around military site	Trespass/ Unauthorised Entry Unauthorised access to secure military area	C	3	17	<ul style="list-style-type: none"> All persons working on site must receive induction and instruction on hazards prior to being authorised to access site. Always carry your contractors pass and vehicle pass if using a vehicle on site. Follow the Aspire Defence Mandatory wearing of PPE as per your site induction – All items of Safe Six mandatory. No photography unless authorised. Do not enter any unauthorised areas. 	C	2	7
	Movement of Persons	Trespass/ Unauthorised Entry Unauthorised personnel entering the work area	C	3	17	<ul style="list-style-type: none"> Heras fence the work area. Secure the worksite and place notices to warn of the work. Give way to marching troops. 	C	2	7
	Movement of Military Vehicles	Struck by Object (vehicle) Collision with military vehicles	D	3	18	<ul style="list-style-type: none"> Plan the route – follow the designated vehicle routes and use pedestrian pathways. Only stop/park in designated areas. Ensure that vehicles are fitting with working flashing beacon Obey the speed limits within the barrack compound. Give way to tanks/large military vehicles at all times, the driver may not be able to see you 	D	1	9
	Working on MOD sites	People Areas of work near MOD personnel	C	3	17	<ul style="list-style-type: none"> Use of the utilities impact notification system to agree work locations so that Military and our vehicles cannot be in the same place at the same time. Ensure that you have your pass on you at all times. Be prepared to show your pass when requested by MoD police, guards or other Tidworth personnel. Do not take any photographs unless authorised. This includes mobile phone cameras. 	C	2	7

	Generic Task Based Risk Assessment Working on Military Sites	Reference:	ISA 03 v14.0
	For: UK Power Networks Services	Review Dates:	01/11/2027

	STEPS	HAZARDS	Unmitigated			CONTROL MEASURES	Mitigated		
			C	L	R		C	L	R
	Escalation in security level Heightened security leading to more extensive checks when entering MOD property.	Violence Risk of force being used to apprehend suspicious persons	C	3	17	<ul style="list-style-type: none"> If challenged, stop any activity and comply with instruction. Follow the instructions of military personnel and site rules in an event of security escalation. 	C	2	7
	Movement around Aspire Defence Capital Works construction tiles.	Struck by moving plant. UKPNS staff being struck by moving Plant	D	4	18	<ul style="list-style-type: none"> Stick to the pedestrian walkways Ensure that staff always wear proximity sensors provided at project office sign in. Always wear appropriate hi-vis clothing. 	D	1	9
Produced by: Kath Rainbow		Signature: Kath Rainbow	Date: 03/10/2024		Approved by: Chris Shackell		Signature:	Date: 01/11/2024	

C – Consequence L – Likelihood R – Risk

Specific PPE/Fit for Work requirements stated in the Control Measures are mandatory.

An On-site (Point of Work) Assessment or Dynamic Assessment must be undertaken for all tasks to confirm which items of Safe 6 to be used and any additional PPE/Equipment required as a result of the site conditions.

TRMT/SAT Attendees	Reason for Review	Actions Required	Details of changes
Lisa Sandle Kath Rainbow	Periodic review	None	Removed epidemic/pandemic risks